



B-2 LEVEL REPLACEMENT QUANTITY SCHEDULE	
AREA	REPLACEMENT FIREPROOFING QUANTITY
SOUTH	452 SQUARE FEET OF FIREPROOFING

#### NOTES

1. FIREPROOFING MATERIAL SHALL BE HIGH DENSITY CEMENTITIOUS, THICKNESS SHALL PROVIDE THE FOLLOWING FIRE PROTECTION:  
 - BEAMS 2 HRS.  
 - COLUMNS AND GIRDERS 3 HRS.  
 - DIAGONAL BRACING 3 HRS.
2. PROVIDE UL TEST DATA FOR ALL SUBMITTED PRODUCTS AND THICKNESS.
3. ALL STEEL MEMBERS ARE TO BE CONSIDERED "RESTRAINED" FOR UL DATA.

#### LEGEND

 AREAS TO BE RE-FIREPROOFED